BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/09/2013-14, Date: 10.12.2013 **ITEM NO:09**

SCHEDULE-B

NAME OF WORK: Improvements to Drain & Footpath 11th cross Right Side Bhuvaneshwari Nagara in Bagalagunte ward No 14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **H C SIDDEGOWDA**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications	Cum	60.2	90.72	Rupees Ninety and Seventy Two Paise Only
2	Removing B.S.Slab of drain and stacking etc., complete as per specifications		81.27	50.11	Rupees Fifty and Eleven Paise Only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	19.19	4211.38	Rupees Four Thousand Two Hundred Eleven and Thirty Eight Paise Only
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	11.1	4690.5	Rupees Four Thousand Six Hundred Ninety and Fifty Paise Only
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete as per specifications	Sqm	81.27	70.04	Rupees Seventy and Four Paise Only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete as per specifications	Sqm	54.18	343.44	Rupees Three Hundred Forty Three and Forty Four Paise Only

Signature of the Contractor

Executive Engineer

	ding and constructing precast concrete solid blocks with pressive strength not les than 35 Kg/sqm with cement rtar 1:4 masonry (quoin, Jamb, closer blocks) with solid ncrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	120.4	924.48	Rupees Nine Hundred Twenty Four and Forty Eight Paise Only
8	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications	Sqm	135.45	1600.0	Rupees One Thousand Six Hundred Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications	Cum	60.2	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,